VANI VILAS HOSPITAL, MYSORE.

Notice dated 25th March 1939.

The public are hereby informed that the Vani Vilas Hospital, Mysore, will be shifted to the New Building, Cheluvamba Hospital for Women, Irwin Road, Mysore, on the 30th March 1939 at Mid-day Admission of new patients in the New Hospital will be made after 12 Noon.

K. S. CAPTAIN,
Medical Officer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated 19th November,* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notice, dated 13th March 1939.

The attention of the public is invited to the Notification calling for the labour portion of the work of laying pipe lines for improvement of water supply to Shimoga Town, published in pages 534-536 Part VI of the *Mysore Gazette,* dated 16th March 1939.

The last date of receiving tenders is fixed on 5th April 1939.

Notification dated 16th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 10th April 1939, for the labour portion of the work for laying pipe lines for water supply to Sagar town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 520 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for the labour portion of the work for laying pipe lines for water supply to Sagar town," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Estimate of the approximate quantities for the labour portions of the work for laying pipe lines for water-supply to Sagar Town.

No.	Items of work	Unit	Quantity
	Distribution System.		
1	Earthwork excavating the pipe trench in all soils and refilling, watering and tamping, etc., including clearing site	C.yd.	2,104
2	Making lead joints to 4″ C.I. pipes including laying jointing and conveying to site, etc., complete	Joints	195
3	Do 3″ C.I. pipes do	,,	762
4	Do $2\frac{1}{2}$″ C.I. pipes do	,,	155
5	Laying and jointing 5″ G.I. pipes with lead for outlet from service reservoir including necessary earth work	R.ft.	72
6	Laying and jointing 2″ G.I. pipes including cutting and threading earthwork and fixing of specials, etc., complete	,,	300
7	Do $1\frac{1}{2}$″ G.I. pipes do	,,	1,900
8	Do 1″ do do	,,	3,850
9	Do $\frac{3}{4}$″ G.I. pipes do	,,	1,000
10	Constructing gland cock cisterns as per type design	No.	14
11	Constructing platform for public taps as per type design	,,	30
12	Constructing valve cisterns as per type design	,,	10
	5″ C. I. Rising Main.		
1	Earthwork excavating the pipe trench in all soils and refilling, watering and tamping, etc., including clearing site	C.yd.	1,099
2	Conveying, making lead joints to 5″ C.I. pipes and specials including laying and jointing with cuts, etc., complete	Joint	368
3	Laying and jointing to 5″ G.I. pipes with lead including cutting and threading	R.ft.	60
4	Constructing valve cisterns as per type designs	No.	4

Notification dated 20th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 12th April 1939, for constructing a suction well for water-supply to Belur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing a suction well for water-supply to Belur Town, in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders. will be returned

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of constructing a Suction Well for water-supply to Belur Town.

No.	Particulars	Unit	Quantity
	Suction well of 12′ diameter and 15′ depth.		
1	Providing and assembling at spot an R. C. C. curb of 1½′ thick including cutting edge, etc., complete, as per design for sinking a well of 12′ diameter	No.	1
2	Earthwork excavation in all soil for the well :—I fathom	C.yd.	39
	II fathom ..	,,	39
	III fathom	,,	20
3	Steining the well with burnt brick in cement mortar in the proportion of 1 : 6	C.ft.	1,076
4	Steining with R. C. C. curb at each fathom depth of well	C.ft.	96
5	Cement plastering ½″ thick for the steining	Sqr. .	9.90
6	Expanded metal frame work including locking arrangements	S.ft.	177
7	Rough stone revetment dry, including jelly packing alround the well ..	C.yd.	50

Notification, dated 20th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 12th April 1939, for the labour portion of work for laying pipe lines for water-supply to Belur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 475 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the labour portion of work for laying pipe lines for water-supply to Belur Town, in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Approximate quantities for the labour portion of work for laying pipe lines for water supply to Belur Town.

Sl. No.	Particulars	Unit	Quantity
	Distribution System.		
1	Earthwork excavating the pipe trench and refilling, watering, tamping, etc., complete in all soils for laying C. I. pipes	C.yd.	1,497
2	Making lead joints to 3″ C. I. pipes including laying and jointing and conveying to spot	Joints	500
3	Laying and jointing 1½″ G. I. pipes with cuts and threads including earthwork, etc., complete	R.ft.	4,340
4	Do do 1″ G. I. pipes do do ..	,,	5,105
5	Do do ¾″ do do do ..	,,	2,100
6	Fixing 3″ sluice valves	..	2
7	Constructing valve cisterns as per type design	..	2
8	Constructing platforms for public fountains as per type designs	..	20
9	Constructing gland cock cisterns as per type design	..	30
10	Unloading the C. I. pipes from the railway wagons at Hassan Railway Station, loading and carting to Belur Town and stacking along the proposed lines in heaps of 12 each at a distance of 100′ from heap to heap ..	Cwt.	560
	Laying 4″ C. I. Rising Main.		
1	Earthwork excavating the pipe trench and refilling the same with watering and consolidation for laying C. I. pipes	C.yd.	600
2	Making lead joints to 4″ C. I. pipes including laying and conveying to work spot	Joints	200
3	Unloading from the wagon, loading, carting from the railway station at Hassan to Belur and stacking in heaps of 10 each at a distance of 120′ from heap to heap along the proposed rising main line from pump house to elevated tank	Cwt.	300
4	Constructing valve cisterns as per type design	No.	2

Notification dated 24th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 1st April 1939 for constructing drains in Konanur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 257 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing drains in Konanur" in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of constructing drains in Konanur Town.

No.	Particulars	Unit	Quantity
	Constructing silk pattern drains with new check slabs on 3″ surki concrete and 1½″ thick cement concrete for bed and sides of gutter portion and surface plastered with ½″ cement plastering including cement pointing the joints of slabs and earthwork excavation, etc., complete :—		
1	Design of 3″ section	R.ft.	1,860
2	Do 4″ (1) Section	,,	475
3	Do ... 4″ (2) Section	,,	470

N. KRISHNIENGAR,
Sanitary Engineer.

OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, BANGALORE CIRCLE, BANGALORE.

Abstract Notification.

The attention of the public is drawn to Gazette Notification dated 13th March 1939, *re* the auction sale of Mango Crop at the Ramakrishna Krishi Sala, Anekal Taluk, on 5th April 1939, at 2 P.M. by the Head Master of the Institution, published on pages 530 and 531, Part VI of the *Mysore Gazette*, dated 16th March 1939.

B. DASAPPA.
Assistant Director.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Abstract Notification dated 14th March 1939.

Attention of the public is invited to this office Notification No. 5, dated 12th March 1939, calling for tenders for constructing a poultry house at the Rural Welfare Centre at Closepet, published in the *Mysore Gazette*, Part VI, dated 16th March 1939, page 531.

Notification No. 6 of 1938-39, dated 20th March 1939.

1. Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, up to 2 P.M. on 15th April 1939 for repairs to cattle stall on the Cattle Breeding Station, Ajjampur.

2. An approximate estimate of quantities for the above work is given below. These quantities are not guaranteed. The work should be completed within one month from the date of acceptance of tender.

3. Earnest money of Rs. 25 in cash should be remitted under Revenue Deposit at the State Huzur Treasury, Bangalore, with a challan duly filled in by tenderers. The tender should be superscribed "Repairs to Cattle Stall on the Cattle Breeding Station, Ajjampur." The tenders will be opened at 2-30 PM. on 15th April 1939.

4. Subject to the formal sanction of the Director of Agriculture the acceptance of any tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of five per cent of the value of the work and to execute the usual contract bond in default of which his tender will be considered as cancelled, and the security deposit will be forfeited.

6. The name of the successful competitor whose tender has been accepted will be notified in due course.

7. After the acceptance of the successful tender the earnest money deposited on the refused tenders will be arranged to be returned to the parties.

8. Rates over the tendered rates will on no account be enhanced.

9. Quotations must be written both in words as well as in figures.

10. The measurements checked by the Agricultural Engineer will have to be accepted as final.

Approximate quantity of works.

1.	Flooring with cement concrete 2″ thick and rough plastered with cement after removing existing flooring	18·5 Sqs.
2.	Providing a drain in cement concrete 2″ thick and cement plastered	236 R.ft.
3.	Reinforcing the broken pipe structure with new pipe for bottom and fixing in cement concrete below floor level	15 ,,
4.	Removing the existing plastering and replastering with cement inside to cross wall	1·6 Sqrs.
5.	Patch plastering with chunam	2 Sqs.

M. G. SINGARACHAR,
Agricultural Engineer.